

Construction Site NPDES Compliance - The Perspective of a Construction Manager

Ali Pirouzian, PE - San Diego County Public Works

Dave Sluga, PE - TRC Companies



**Thoughts for the
Construction Manager
from Folks
that Specialize in**

NPDES Compliance at Construction Sites



This Morning's Thoughts

- Quick Review of BMP Implementation & Monitoring for Each Risk Level
- New Draft Construction General Permit – What's New?
- Planning and BMPs for County of San Diego CIP Projects
- Enforcement Actions – San Diego RWQCB
- Storm Drain Inlet Protection
- Soil Cover on Active Disturbed Soil Areas (DSAs)
- The Annual Report and Monitoring Documentation
- Constructability / Budgeting Review

Dave Sluga

Construction Manager Caltrans (1992)

Assisted with Caltrans Storm Water Program (1997)

Assisted Others with NPDES, Smaller Projects (2004)

Construction Manager Consultant (2009)

Stormwater IQA Manager Caltrans & S.D. County (2014)



BMP Implementation Requirements

- Risk Level 1
 - B. Good Site Management “Housekeeping”**
 - C. Non-Storm Water Management**
 - D. Erosion Control – Wind, Cover Inactive DSAs, Limit Use of Plastic**
 - E. Sediment Controls – Effective Perimeter Controls, Stabilized Entrances**
 - F. Run-on and Run-off (-through) Controls**

BMP Implementation Requirements

- Risk Levels 2 and 3
 - A. **Effluent Standards – Sediment and pH**
 - B. Good Site Management “Housekeeping”
 - C. Non-Storm Water Management
 - D. Erosion Control – Wind, Cover Inactive DSAs, Limit Use of Plastic
 - E. Sediment Controls – Effective Perimeter Controls, Stabilized Entrances, **Cover Active DSAs, Face of Slope Interrupters, More Tracking Controls, Maintain various BMPs including DI Protection**
 - F. Run-on and Run-off (-through) Controls

Monitoring Requirements

- Risk Level 1
 - Weekly Inspections plus Observations and Sampling & Analysis

I. Risk Level 1 Monitoring and Reporting Requirements

Table 1- Summary of Monitoring Requirements

Risk Level	Visual Inspections					Sample Collection	
	Quarterly Non-storm Water Discharge	Pre-storm Event		Daily Storm BMP	Post Storm	Storm Water Discharge	Receiving Water
		Baseline	REAP				
1	X	X		X	X		

QRE

* Non-Visible Pollutant Sample Collection

Monitoring Requirements

- Risk Level 2 as a RL 1 plus;
 1. Weekly Inspections plus Observations and Sampling & Analysis

I. Risk Level 2 Monitoring and Reporting Requirements

Table 2- Summary of Monitoring Requirements

Risk Level	Visual Inspections					Sample Collection	
	Quarterly Non-storm Water Discharge	Pre-storm Event		Daily Storm BMP	Post Storm	Storm Water Discharge	Receiving Water
		Baseline	REAP				
2	X	X	X	X	X	X	

QRE

POP

* Non-Visible Pollutant Sample Collection

Monitoring Requirements

- Risk Level 3 same as a RL2 plus:
 1. Weekly Inspections plus Observations and Sampling & Analysis

I. Risk Level 3 Monitoring and Reporting Requirements

Table 2- Summary of Monitoring Requirements

Risk Level	Visual Inspections					Sample Collection	
	Quarterly Non-storm Water Discharge	Pre-storm Event		Daily Storm BMP	Post Storm	Storm Water Discharge	Receiving Water
		Baseline	REAP				
3	X	X	X	X	X	X	X ⁴

QRE

POP

* Non-Visible Pollutant Sample Collection

When Triggered

Draft Construction General Permit

- Generally

Removed:

Bioassessment Requirements
 Post-Construction Calculations

3. Los Peñasquitos Lagoon Sediment TMDL

a. All Responsible Dischargers for the Los Peñasquitos Lagoon Sediment TMDL shall provide an estimate of the representative flow rate from their construction site for one precipitation event, each reporting year in addition to complying with this General Permit.
 b. The Responsible Discharger shall submit the representative flow estimate as a PDF attachment to the Annual Report (due in SMARTS no later than September 1 of each year).

NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES)
 GENERAL PERMIT FOR STORMWATER DISCHARGES
 ASSOCIATED WITH CONSTRUCTION AND LAND DISTURBANCE
 ACTIVITIES

ORDER 20XX-XXXX-DWQ
 NPDES NO. CAS000002

This Order was adopted by the State Water Resources Control Board on:	XXXX XX, 20XX
This Order shall become effective on:	July 1, 2021
This Order shall expire on:	June 30, 2026

IT IS HEREBY ORDERED, that this Order supersedes Order 2009-0009-DWQ as amended by Order 2010-0014-DWQ and 2012-0006-DWQ except for: (1) the requirement to submit annual reports by September 1, 20XX, and (2) enforcement purposes. The Discharger shall comply with the requirements in this Order to meet the provisions contained in Division 7 of the California Water Code (commencing with Section 13000) and regulations adopted thereunder, and the provisions of the federal Clean Water Act and regulations and guidelines adopted thereunder.

I, Jeanine Townsend, Clerk to the Board, do hereby certify that this Order with all attachments is a full, true, and correct copy of an Order adopted by the State Water Resources Control Board, on XXXX XX, XXXX.

AYE:
 NAY:
 ABSENT: None
 ABSTAIN: None

Draft Construction General Permit

- Generally Added:

**Passive Treatment System (e.g. floc logs, spray tackifiers)
Requirements**

TMDL Requirements

Widens the Authorized Construction Dewatering Discharges

Tightens up Requirements for Construction Site Debris and Trash

No Averaging – NALs pH between 6.5-8.5 and Turbidity \leq 250 NTUs

NELs only apply to ATS

Better Defines the Roles of the LRP, QSD (Wider Role), and QSP (Oversight)

More Complicated SWPPP



Draft Construction General Permit

- Risk Level 1
 - A. Effluent Standards - **NALs for Dewatering Discharges**
 - B. Good Site Management “Housekeeping” - **Minor Additions**
 - C. Non-Storm Water Management
 - D. Preserve Native Topsoil**
 - E. Erosion Control – **Run-on and Run-off Controls, Downstream Erosion**
 - F. Sediment Controls
 - G. Surface water Buffer**
 - H. Pesticides Application**
 - I. Demolition of Existing Structure**

Draft Construction General Permit

- Risk Levels 2 and 3
 - A. Effluent Standards – **NALs & NELs for Discharges Subject to TMDLs**
 - B. Good Site Management “Housekeeping”
 - C. Non-Storm Water Management
 - D. Preserve Native Topsoil
 - E. Erosion Control
 - F. Sediment Controls – **RUSLE2 Calculations. Proving BMPs (Sediment Loss versus Natural Conditions)**
 - G. Surface water Buffer
 - H. Pesticides Application
 - I. Demolition of Existing Structure

Draft Monitoring Requirements

- Risk Level 1

1. Weekly Inspections plus Observations and Sampling & Analysis

K. Risk Level 1 Monitoring and Reporting Requirements

Table 1 - Summary of Monitoring Requirements

Risk Level	Visual Inspections				Sample Collection		
	Weekly	Pre-Precipitation Event	Daily Extended Precipitation Event BMP	Post Precipitation Event	Stormwater Discharge	Receiving Water	Non-Visible (when applicable)
1	X	X	X	X			X

Photos of Issues

No more Qualified Rain Event – All Precipitation that Causes Runoff
No Quarterly NSW Discharges to be included in all Inspections

Draft Monitoring Requirements

- Risk Level 2 same as RL1 plus:
 1. Weekly Inspections plus Observations and Sampling & Analysis

Discharge

POP

M. Risk Level 2 Monitoring and Reporting Requirements

Table 2 - Summary of Monitoring Requirements

	Visual Inspections				Sample Collection		
Risk Level	Weekly	Pre-Precipitation Event	Daily Extended Precipitation Event BMP	Post Precipitation Event	Stormwater Discharge	Receiving Water	Non-Visible (when applicable)
2	X	X	X	X	X		X

Photos of Issues

No more Qualified Rain Event – All Precipitation that Causes Runoff

No Quarterly NSW Discharges to be included in all Inspections

No more REAPs - REAP Information in Pre-Precipitation Event Inspections

Draft Monitoring Requirements

- Risk Level 3 same as RL2 plus:
 1. Weekly Inspections plus Observations and Sampling & Analysis

M. Risk Level 3 Monitoring and Reporting Requirements							
Table 2 - Summary of Monitoring Requirements							
Risk Level	Visual Inspections				Sample Collection		
	Weekly	Pre-Precipitation Event	Daily Extended Precipitation Event BMP	Post Precipitation Event	Stormwater Discharge	Receiving Water (when applicable)	Non-Visible (when applicable)
3	X	X	X	X	X	X	X

Photos of Issues

No more Qualified Rain Event – All Precipitation that Causes Runoff
 No Quarterly NSW Discharges to be included in all Inspections
No more REAPs - REAP Information in Pre-Precipitation Event Inspections

Discharge

POP

Draft Monitoring Requirements

- Risk Levels 2 and 3
1. Minimum 3 Samples per Day of the Precipitation Event
 2. First Sample within the first 2 hours of discharge (Business Hours)
 3. Minimum 2 hours Interval for subsequent samples (Business Hours)

Parameter	Test Method / Protocol	Discharge Type	Method Detection Limit	Reporting Units	Numeric Action Level (NAL)	Numeric Effluent Limitation (NEL)
pH	Field test with calibrated portable instrument	Risk Level 2 Discharges other than ATS	0.2	pH units	lower NAL = 6.5 upper NAL = 8.5	N/A
		For ATS discharges	0.2	pH units	N/A	lower NEL = 6.0 upper NEL = 9.0
Turbidity	EPA 0180.1 and/or field test with calibrated portable instrument	Risk Level 2 Discharges other than ATS	1	NTU	250 NTU	N/A
		For ATS discharges	1	NTU	N/A	10 NTU for Daily Weighted Average & 20 NTU for Any Single Sample

San Diego County Public Works – Construction Engineering Planning and BMPs for CIP Projects

- Ali Pirouzian, PE, PEng, CPESC, QSD/QSP - San Diego County Public Works



Experience

- Senior Civil Engineer - San Diego County Public Works Construction Engineering (13 years)
- Private Sector (14 years)
 - Vertical
 - Horizontal
- Stormwater Permit Coordinator – Construction Engineering



Stormwater Reports:

A) General	1. Resident Engineer Stormwater Permit Checklist for Risk Level 1 (Form CE 2011) (rev. 01/04)
	2. NPDES Construction General Permit Requirement Summary Risk Level 1 (Form CE 2012) (rev. 01/04)
	3. Resident Engineer Stormwater Permit Checklist for Risk Level 2 (Form CE 2011) (rev. 01/04)
	4. NPDES Construction General Permit Requirement Summary Risk Level 2 (Form CE 2012) (rev. 01/04)
	5. Resident Engineer Stormwater Permit Checklist for Risk Level 3 (Form CE 2011) (rev. 01/04)
	6. NPDES Construction General Permit Requirement Summary Risk Level 3 (Form CE 2012) (rev. 01/04)
B) Site Inspections	7. Stormwater Site Inspection Report (Form CE 2009) (rev. 01/04)
	8. Stormwater Best Management Practices (BMP) Status Report (Form CE 2011) (rev. 01/04)
	9. Stormwater Site Inspection Report Construction Activity Summary (Form CE 2012) (rev. 01/04)
	10. Post Storm Event Visual Site Inspection Report (Form CE 2009) (rev. 01/04)
	11. During Storm (24-hour Interval) Site Inspection Report (Form CE 2009) (rev. 01/04)
	12. Post Storm Event Visual Site Inspection Report (Form CE 2009) (rev. 01/04)
	13. Quarterly Non-Stormwater Discharge Site Inspection Report (Form CE 2009) (rev. 01/04)
	14. Post Storm Event Visual Site Inspection Report (Form CE 2009) (rev. 01/04)
	15. Secondary Containment and Spill Kit Inventory Report (Form CE 2008) (rev. 01/04)
C) Training	16. Stormwater Training Record (Form CE 2008) (rev. 01/04)
	17. Stormwater Training Log (Form CE 2008) (rev. 01/04)
D) Preparation	18. Non-Event Action Plan (NEAP) – Grading & Land Development/Street and Utilities/Vertical Construction Phase (Form CE 2004) (rev. 01/04)
	19. NEAP – Road Establishment/Other Landscaping Phase (Form CE 2004) (rev. 01/04)
	20. NEAP – Inactive Site (Form CE 2004) (rev. 01/04)
	21. NEAP Amendment Log and Certification (Form CE 2004) (rev. 01/04)
E) Sampling	22. Sample Information, Identification, Chain-of-Custody Record (Form CE 2009) (rev. 01/04)
	23. Stormwater Sample Laboratory Test Report (Form CE 2011) (rev. 01/04)
	24. Non-Volatile Polychlorinated Biphenyl Sampling and Analysis Report (Form CE 2009) (rev. 01/04)
	25. Stormwater Discharge Sample Log and Test Report (Form CE 2009) (rev. 01/04)
	26. Stormwater Sampling and Analysis Report (Form CE 2009) (rev. 01/04)
	27. Bio-assessment (Form CE 2009) (rev. 01/04)
	28. Qualifying Test: Turbidity Sampling and Analysis Report (Form CE 2009) (rev. 01/04)
	29. Stormwater Turbidity Meter Calibration Record (Form CE 2009) (rev. 01/04)
	30. Stormwater pH Meter Calibration Record (Form CE 2009) (rev. 01/04)
F) Notifications	31. Notice of Discharge Report (High Level Non-Compliance) (Form CE 2008) (rev. 01/04)
	32. Notice of Discharge Report / Low Level Non-Compliance Report (Form CE 2008) (rev. 01/04)
	33. NAL Surveillance Report (Form CE 2008) (rev. 01/04)
	34. Annual Report Checklist (Form CE 2008) (rev. 01/04)

You can find all the Stormwater forms and logs on the San Diego County Engineering Section's website at: <http://www.sdcgov.org/Engineering/Stormwater/Forms>



San Diego County Public Works Projects

- Average 3 to 4 SWPPP (>1 acre) projects per year with ranging from between \$1M to \$25M (2 projects last FY)
- Average 30 WPCP (<1 acre) projects per year with ranging \$15K to \$5M (38 projects last FY)
- We own the projects.



Key Ingredients

- Each project is given the tools for proper implementation water pollution controls
 - Detailed specifications within the contract documents.
 - SWPPP Templates for different Risk Levels and LUPs
 - Identify the work and provide method of payment.
- All BMPs are paid by item unit price ensuring the contractor gets paid for work done right.
- Standard Plans for BMPs to ensure correct installations.
 - Contract allows to add bid items and pay contractors by writing a change order if any BMPs is missed or something else would work better.

Date: 7/05/2016
Time: 10:51 am

County of San Diego - Public Works (Flood Cntrl)

Page 2 of 7

PROJECT PAY ESTIMATE

Project: WOODSIDE AVENUE FLOOD CONTROL IMPROVEMENTS
Engineer: Cacho

Estimate No. 18
PO Number:
Total Authorized: \$15,222,700.18

6/22/2016 - 6/30/2016

Item No.	Description	U/M	Contract			Previous			This Estimate			Total Work Completed		Percent Complete
			Quantity	Unit Price	Total Price	Qty	Qty	Amount	Qty	Amount	Qty	Amount		
019	STRUCTURE BACKFILL (F)	CY	3,419.0000	40.0000	136,760.00	2,136.0000	0.0000	0.00	2,136.0000	85,440.00	0.00	2,136.0000	85,440.00	62
020	DEWATERING SYSTEM	LS	1.0000	120,000.0000	120,000.00	1.0000	0.0000	0.00	1.0000	120,000.00	0.00	1.0000	120,000.00	100
021	PREPARE SWPPP	LS	1.0000	5,100.0000	5,100.00	0.8000	0.0000	0.00	0.8000	4,080.00	0.00	0.8000	4,080.00	80
022	RAIN EVENT ACTION PLAN (REAP)	EA	40.0000	500.0000	20,000.00	22.0000	0.0000	0.00	22.0000	11,000.00	0.00	22.0000	11,000.00	55
023	STORM WATER ANNUAL REPORT	EA	3.0000	2,000.0000	6,000.00	1.0000	0.0000	0.00	1.0000	2,000.00	0.00	1.0000	2,000.00	33
024	STORM WATER SAMPLING AND ANALYSIS	DAY	30.0000	600.0000	18,000.00	16.0000	0.0000	0.00	16.0000	9,600.00	0.00	16.0000	9,600.00	53
025	BMP MAINTENANCE PERIOD (90 DAYS)	DAY	90.0000	100.0000	9,000.00	0.0000	0.0000	0.00	0.0000	0.00	0.00	0.0000	0.00	0
026	MOVE IN/MOVE OUT (EROSION CONTROL)	EA	10.0000	500.0000	5,000.00	0.0000	0.0000	0.00	0.0000	0.00	0.00	0.0000	0.00	0
027	EROSION CONTROL (BONDED FIBER MATRIX)	SY	4,000.0000	1.4000	5,600.00	3,805.0000	0.0000	0.00	3,805.0000	5,327.00	0.00	3,805.0000	5,327.00	95
028	EROSION CONTROL (TYPE D)	SY	10,202.0000	1.4000	14,282.80	0.0000	0.0000	0.00	0.0000	0.00	0.00	0.0000	0.00	0
029	BMP MAINTENANCE COST SHARING	DLR	50,000.0000	1.0000	50,000.00	22,538.1500	0.0000	0.00	22,538.1500	22,538.15	0.00	22,538.1500	22,538.15	45
030	CONSTRUCTION SITE MANAGEMENT	LS	1.0000	10,000.0000	10,000.00	0.7500	0.0000	0.00	0.7500	7,500.00	0.00	0.7500	7,500.00	75
031	STREET SWEEPING	LS	1.0000	44,000.0000	44,000.00	0.7500	0.0000	0.00	0.7500	33,000.00	0.00	0.7500	33,000.00	75
032	TEMP. STABILIZED CONST. ENTR.	EA	10.0000	1,000.0000	10,000.00	5.0000	0.0000	0.00	5.0000	5,000.00	0.00	5.0000	5,000.00	50
033	TEMPORARY GRAVEL BAG	EA	5,000.0000	2.5000	12,500.00	2,037.0000	0.0000	0.00	2,037.0000	5,092.50	0.00	2,037.0000	5,092.50	41
034	TEMPORARY CONCRETE WASHOUT (PORTABLE)	EA	10.0000	500.0000	5,000.00	3.0000	0.0000	0.00	3.0000	1,500.00	0.00	3.0000	1,500.00	30
035	TEMPORARY SILT FENCE	LF	1,538.0000	3.0000	4,614.00	1,792.0000	0.0000	0.00	1,792.0000	5,376.00	0.00	1,792.0000	5,376.00	117
036	TEMPORARY SILT FENCE	EA	10.0000	200.0000	2,000.00	4.0000	0.0000	0.00	4.0000	800.00	0.00	4.0000	800.00	40

Date: 7/05/2016

County of San Diego - Public Works (Flood Cntrl)

Page 5 of 7

PROJECT PAY ESTIMATE

Project: WOODSIDE AVENUE FLOOD CONTROL IMPROVEMENTS
Engineer: Cacho

Estimate No. 18
PO Number:
Total Authorized: \$15,222,700.18

6/22/2016 - 6/30/2016

Item No.	Description	U/M	Contract			Previous			This Estimate			Total Work Completed		Percent Complete
			Quantity	Unit Price	Total Price	Qty	Qty	Amount	Qty	Amount	Qty	Amount		
043	ASPHALT C	SF	143.0000	3.0000	429.00	0.0000	0.0000	0.00	0.0000	0.00	0.0000	0.00	0	
112	RELOCATE STREET LIGHT	EA	1.0000	5,000.0000	5,000.00	0.0000	0.0000	0.00	0.0000	0.00	0.0000	0.00	0	
113	MODIFY TRAF. SIG. & SFTY LIT. SYS	LS	1.0000	110,000.0000	110,000.00	0.5500	0.0000	0.00	0.5500	60,500.00	0.00	0.5500	60,500.00	55
114	PAVEMENT MARKER, RETROREFLECTIVE	EA	122.0000	5.0000	610.00	189.0000	0.0000	0.00	189.0000	945.00	0.00	189.0000	945.00	155
115	CURB INLET FILTER	EA	3.0000	3,200.0000	9,600.00	0.0000	0.0000	0.00	0.0000	0.00	0.00	0.0000	0.00	0
116	FIELD ORDERS	DLR	100,000.0000	1.0000	100,000.00	63,962.1600	0.0000	0.00	63,962.1600	63,962.16	0.00	63,962.1600	63,962.16	64
117	TIME RELATED OVERHEAD	WDY	540.0000	2,000.0000	1,080,000.00	288.0000	0.0000	0.00	288.0000	576,000.00	0.00	288.0000	576,000.00	53
118	PROGRESS SCHED.(CRITICAL PATH)	LS	1.0000	8,500.0000	8,500.00	0.7500	0.0000	0.00	0.7500	6,375.00	0.00	0.7500	6,375.00	75
119	8" PVC PIPE STORM DRAIN	LF	43.0000	45.0000	1,935.00	114.0000	0.0000	0.00	114.0000	5,130.00	0.00	114.0000	5,130.00	265
120	2" AIR RELEASE VALVE	EA	1.0000	3,500.0000	3,500.00	1.0000	0.0000	0.00	1.0000	3,500.00	0.00	1.0000	3,500.00	100
121	TEMPORARY FIBER ROLL	LF	5,000.0000	4.0000	20,000.00	1,631.0000	0.0000	0.00	1,631.0000	6,524.00	0.00	1,631.0000	6,524.00	33
122	TEMPORARY COVER	SY	3,000.0000	5.0000	15,000.00	7,800.0000	0.0000	0.00	7,800.0000	39,000.00	0.00	7,800.0000	39,000.00	260
123	Material On Hand - Waterline Relocations	DLR	395,835.7000	1.0000	395,835.70	0.0000	0.0000	0.00	0.0000	0.00	0.00	0.0000	0.00	0
124	Material On Hand - 48" Waterline Relocations & Precast RCB	DLR	468,299.0000	1.0000	468,299.00	33,123.4000	0.0000	0.00	33,123.4000	33,123.40	0.00	33,123.4000	33,123.40	7
125	Material On Hand-Precast RCB	DLR	173,035.4400	1.0000	173,035.44	173,035.4400	0.0000	0.00	173,035.4400	173,035.44	0.00	173,035.4400	173,035.44	100
126	Material On Hand - Precast RCB 15x5.5	DLR	193,332.3300	1.0000	193,332.33	193,332.3300	0.0000	0.00	193,332.3300	193,332.33	0.00	193,332.3300	193,332.33	100
127	Certified Payroll Retention Per Sec. 7-1.01A(3)-3-15-16	LS	1.0000	-10,000.0000	-10,000.00	0.0000	0.0000	0.00	0.0000	0.00	0.00	0.0000	0.00	0
128	Material On Hand - Precast RCB	DLR	63,773.6200	1.0000	63,773.62	63,773.6200	0.0000	0.00	63,773.6200	63,773.62	0.00	63,773.6200	63,773.62	100
129	Material On Hand - Precast RCB 15x5.5	DLR	341,959.2700	1.0000	341,959.27	341,959.2700	0.0000	0.00	341,959.2700	341,959.27	0.00	341,959.2700	341,959.27	100

Change Orders

Change Order: 01 Revise Cox Communications Utility Plans

01-01	Revise Cox Communications Utility Plans	LS	1.0000	13,653.0000	13,653.00	1.0000	0.0000	0.00	1.0000	13,653.00	100
-------	---	----	--------	-------------	-----------	--------	--------	------	--------	-----------	-----

Change Order: 02 JOINT TRENCH CONFLICT WITH 8" GASLINE

02-01	CREDIT FOR JOINT TRENCH CHANGE	LS	1.0000	-7,125.0000	-7,125.00	1.0000	0.0000	0.00	1.0000	-7,125.00	100
02-02	EXTRA WORK AT FORCE ACCOUNT	DLR	60,000.0000	1.0000	60,000.00	60,000.0000	0.0000	0.00	60,000.0000	60,000.00	100

Change Order: 02 S1 Supplement To Change Order No. 02

02 S1	Extra Work At Force Account For CCO2	DLR	3,500.0000	1.0000	3,500.00	3,063.8100	0.0000	0.00	3,063.8100	3,063.81	88
-------	--------------------------------------	-----	------------	--------	----------	------------	--------	------	------------	----------	----

Change Order: 03 Joint Trench Conflict With 42" RCB Culvert

03-01	Extra Work At Agreed Lump Sum Price	LS	1.0000	9,734.4300	9,734.43	1.0000	0.0000	0.00	1.0000	9,734.43	100
-------	-------------------------------------	----	--------	------------	----------	--------	--------	------	--------	----------	-----


Change Order: 04 Anticorrosion Coating System For 36" CML&C Pipe

04-01	Machine Applied Tape Coating System	LS	1.0000	21,000.0000	21,000.00	1.0000	0.0000	0.00	1.0000	21,000.00	100
-------	-------------------------------------	----	--------	-------------	-----------	--------	--------	------	--------	-----------	-----

Key Ingredients

- Knowledgeable and Trained Staff representing San Diego County

- You'll get to hear from a knowledgeable field person in a few minutes.
- Importance of QSD and/or QSP in the field. All RE's (Civil Engineer and Sr. Civil Engineers) of the County are either QSD or QSP.
- Understands the importance of CGP Compliance and S.D. County attitude.
- Understands the job is to construct a quality facility.
- Combine CGP Compliance with construction activities planning to ensure one seamless operation
- Works with the contractor to achieve CGP compliance during construction (goodwill)
- Teamwork



Dashes of This and Pinches of That

- Independent Quality Assurance (IQA) Reviewer
- IQA Review Reports
- Personal site visits
- Sampling & Analysis follow-ups
- Work with San Diego County Watershed Department
- Interaction with Contractors / AGC, Agencies and Consultant
- Other




COUNTY OF SAN DIEGO - Department of Public Works INDEPENDENT QUALITY ASSURANCE (IQA) STORMWATER SITE INSPECTION REPORT GENERAL PERMIT CONSTRUCTION ACTIVITIES			
PROJECT NAME AND SITE ADDRESS: SAN VICENTE ROAD IMPROVEMENT PROJECT SAN VICENTE ROAD AND DEWEY LANE RANCHO, CA 92085		CONTRACT NUMBER: 59899 ORACLE NUMBER: 100952 VIDEO NUMBER: 9.3702550	
CONTRACTOR NAME AND ADDRESS: PLATON CORP 1775 LA COSTA MEADOWS DRIVE SAN MARCO, CA 92078		PROJECT SITE RISK LEVEL: <input type="checkbox"/> Risk Level 1 <input type="checkbox"/> LUP Type 1 <input type="checkbox"/> HROP <input checked="" type="checkbox"/> Risk Level 2 <input type="checkbox"/> LUP Type 2 <input type="checkbox"/> Risk Level 3 <input type="checkbox"/> LUP Type 3	
Water Pollution Control Manager Name and Company Name: Shawn Fisher, QSDM 00112, Platon Creek, Inc.			
General Information			
Inspector's Name: David Sluga, QSDM 00047, Vali Cooper & Associates		Date of Inspection: 09-27-16	
Weather Condition: <input type="checkbox"/> Clear <input type="checkbox"/> Partly Cloudy <input type="checkbox"/> Cloudy	Precipitation Condition: <input type="checkbox"/> Heavy Rain <input type="checkbox"/> Light Rain <input type="checkbox"/> Rain <input type="checkbox"/> Snow	Wind Condition: <input type="checkbox"/> None <input type="checkbox"/> Less than 5 MPH <input type="checkbox"/> Greater than 5 MPH	
Date Last Rain Event Ended:		Total Event Rainfall Amount:	
		Weather Station ID:	



Money Gives CGP Compliance Its Taste

Payments to Contractors to Date

- SWPPP projects (1 acre<) have range between 70K to 825K (1.4% to 10% of the total contract cost)
- WPCP projects have range between 6K to 100K (1% to 14% of the total contract cost)



Recent Enforcements

- **R9-2018-0065: Rail Projects Within the Lossan and Mid Coast Corridor - 2018 (\$36,371)**
- Description of Alleged Violations:
 1. SANDAG violated Water Code section 13376; General Permit Discharge Prohibitions III. A and 111.8 , Section V.A.2 and Attachment D section A.1.b; Basin Plan Waste Discharge Prohibition No. 8; and Federal Water Pollution Control Act (Clean Water Act) (22 U.S.C.§ 1251 et seq.) section 301 (33 U.S.C. § 1311) by pumping sediment laden storm water from the project to Waters of the United States on January 9, 2018.

Rail Projects Within the Lossan and Mid Coast Corridor (SANDAG) - 2018



2. SANDAG violated section B.1.b of Attachment D to the General Permit by failing to berm stockpiled material on site on January 9, 2018.
3. SANDAG violated section E.1 of Attachment D to the General Permit by failing to maintain effective perimeter control at the site and failing to stabilize the construction entrance/exit in a manner that would control sediment discharges from the site on January 9, 2018.
4. SANDAG violated section F of Attachment D to the General Permit by failing to effectively manage all run-on and run-off from the site on January 9, 2018.



Rail Projects Within the Lossan and Mid Coast Corridor (SANDAG)

Photo shows the blue highline from the pump in the impounded sediment laden storm water up the site embankment, and onto Pacific Coast Highway. This photo also shows a lack of perimeter sediment controls, stockpile BMPs, erosion controls or tracking controls at the entrance/exit to the site. Photo shows the impounded storm water on the construction site with the pump in center.



Rail Projects Within the Lossan and Mid Coast Corridor (SANDAG) - 2018

Photos show the
sediment laden storm
water discharged from
the site at Anna Avenue
and Pacific Coast
Highway.



Older Enforcement Actions

DEVELOPER SAN ALTOS-LEMON GROVE ISSUED \$595,367 PENALTY FOR WATER QUALITY VIOLATIONS

[+ Share / Save](#) [f](#) [t](#) [r](#)

August 2016 Articles

San Diego Regional Water Quality Control Board San Altos-Lemon Grove LLC



Source: San Diego Regional Water Quality Control Board

August 30, 2016 (Lemon Grove) -- The San Diego Regional Water Quality Control Board has imposed a \$595,367 penalty for water quality violations related to construction activities at its 18-acre Valencia Hills residential development.

Violations at the Valencia Hills site were brought to the San Diego Water Board's attention by Lemon Grove after its multiple warnings and enforcement efforts directed at the developer were met with minimal response.

Older Enforcement Actions

<https://app.box.com/s/uupy9ckj6ngwul4m4im94lidzyj0hd8g>

Stockpile Management 2016 CASQA “Ask the Regulator”

Christina Arias, PE

San Diego Regional
Water Quality Control Board

Older Enforcement Actions

Water Board Compliance Interpretation

1. Does plastic sheeting meet **Best Conventional Technology (BCT)** standard for stockpiles?
2. When is a stockpile not *actively being used*?

Older Enforcement Actions

CGP Requirement-Erosion Control

- Provision D.3. of Attachment C [or D or E]:
“...dischargers shall **limit the use of plastic materials** when more sustainable, environmentally friendly alternatives exist. Where plastic materials are deemed necessary, the discharger shall consider the use of plastic materials resistant to solar degradation.”

Older Enforcement Actions



July 23, 2015



July 13, 2016



Older Enforcement Actions



Plastic sheeting does not meet BCT standard
in the long term!

Older Enforcement Actions

CGP Requirement-Stockpiles

- Provision B.1.b of Attachment C [or D or E]:
“...dischargers shall implement good site management (i.e., “housekeeping”) measures for construction materials that could potentially be a threat to water quality if discharged...dischargers shall....**[C]over and berm loose stockpiled construction materials that are not actively being used....”**

Older Enforcement Actions

San Diego Water Board Conclusions

- **Unless materials are being moved onto or off of a stockpile, it should be covered and bermed.**



Older Enforcement Actions


What about *actively being used*?

San Diego Water Board Conclusions

- Permit language trumps BMP guidance
- City photos/inspections admissible evidence
- Can infer ongoing violation based on totality of evidence

Storm Drain Inlet Protection

- Storm Drain Inlet is the Beginning of a Separate Conveyance System Designed to a Specific Standard



Fluid - Pipes

Nodes

Runoff Coefficient

Drainage Area

Rainfall Intensity

Rainfall Duration

Rational Equation

Bernoulli Equation

Time of Concentration

Storm Drain Inlet Protection

- Caltrans Hydraulics Manual



830-3
May 7, 2012


Table 831.3
Desirable Roadway Drainage Guidelines

HIGHWAY Type/Category/Feature	DESIGN STORM		DESIGN WATER SPREAD		
	4% (25 yrs)	10% (10 yrs)	Shldr or Parking Lane	1/2 Outer Lane	Local Standard
FREEWAYS					
Through traffic lanes, branch connections, and other major ramp connections.	X	--	X	--	--
Minor ramps.	--	X	X	--	--
Frontage roads.	--	X	--	--	X
CONVENTIONAL HIGHWAYS					
High volume, multilane Speeds over 45 mph.	X	--	X	--	--
High volume, multilane Speeds 45 mph and under.	--	X	--	X	--
Low volume, rural Speeds over 45 mph.	X	--	X	--	--
Urban Speeds 45 mph and under.	--	X	--	--	X
ALL STATE HIGHWAYS					
Depressed Sections That Require Pumping:					
Use a 2% (50 yrs) design storm for freeways and conventional State highways. Design water spread at depressed sections should not exceed that of adjacent roadway sections. A 4% (25 yr) design storm may be used on local streets or road undercrossings that require pumping.					

Storm Drain Inlet Protection

Sediment Control

- Dam - Detain Stormwater and Precipitate Sediment
- Filter – Remove Sediment from Stormwater as it Passes Through



Storm Drain Inlet Protection

CGP and Sediment Control

- All Risk Levels

E. Sediment Controls

1. Risk Level 2 dischargers shall establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from the site.

Area Drain

Storm Drain Inlet Protection

CGP and Sediment Control

- Risk Levels 2 and 3 only

E. Sediment Controls

6. **Additional Risk Level 2 Requirement:** Risk Level 2 dischargers shall ensure that all storm drain inlets and perimeter controls, runoff control BMPs, and pollutant controls at entrances and exits (e.g. tire washoff locations) are maintained and protected from activities that reduce their effectiveness.


Storm Drain Inlet Protection

Caltrans Construction Site BMPs Manual = SC-10

Definition and Purpose	Devices used at storm drain inlets that are subject to runoff from construction activities to detain and/or to filter sediment-laden runoff to allow sediment to settle and/or to filter sediment prior to discharge into storm drainage systems or watercourses.
Appropriate Applications	<ul style="list-style-type: none">■ <u>Where ponding will not encroach into highway traffic.</u>■ Where sediment laden surface runoff may enter an inlet.■ <u>Where disturbed drainage areas have not yet been permanently stabilized.</u>■ Where the drainage area is 0.4 ha (1 ac) or less.■ Appropriate during wet and snow-melt seasons.
Limitations	<ul style="list-style-type: none">■ Requires an adequate area for water to pond without encroaching upon traveled way and should not present itself to be an obstacle to oncoming traffic.


Storm Drain Inlet Protection

- Caltrans Standard Plan T- 61




Storm Drain Inlet Protection

- Caltrans Standard Plan T- 62




Storm Drain Inlet Protection

- Caltrans Standard Plan T- 63



Storm Drain Inlet Protection

- Caltrans Standard Plan T- 64



Storm Drain Inlet Protection

- Caltrans Standard Specifications 13-6.02B Rigid Plastic Barriers

A rigid plastic barrier must:

For an inlet with a curb opening but no grate, the rigid plastic barrier must be sized to fit the opening and have: _____

1. Horizontal flap of at least 6 inches with an under-seal gasket to prevent underflows
2. High-flow bypass
3. Vertical height of at least 7 inches after installation


For a grated inlet without a curb opening, the rigid plastic barrier must be sized to fit the inlet and:

1. Cover the grate by at least 2 inches on each side and have an under-seal gasket to prevent underflows
2. Have a high-flow bypass
3. Have a vertical height of at least 1.5 inches after installation

For a grated inlet with a curb opening, the rigid plastic barrier must be sized to fit and have:

1. Horizontal flap that covers the grate by at least 2 inches on the 3 sides away from the curb opening and must have an under-seal gasket to prevent underflows
2. High-flow bypass
3. Section that covers at least 5 inches vertically above the flow line of the curb opening after installation

Storm Drain Inlet Protection



Planned



Actual

Storm Drain Inlet Protection



Actual



Actual

Storm Drain Inlet Protection



Actual



Actual

Storm Drain Inlet Protection



Actual



Actual

Storm Drain Inlet Protection



Actual



Actual

Storm Drain Inlet Protection



Actual



Actual

Storm Drain Inlet Protection

- **High-Flow Bypass:** Furnish low profile curb & grate inlet protection device with vertical filter height of 2 +/- 0.33 vertical inches to provide for a high-flow bi-pass. When water reaches the vertical height of the filter, the device shall allow water to flow over the filter with minimum impedance into the storm drain inlet.



Actual

Storm Drain Inlet Protection



Actual



Actual

Storm Drain Inlet Protection



Actual



Actual

Storm Drain Inlet Protection

- https://www.sandiego.gov/sites/default/files/2018_sws_part_2_public_outreach.pdf

**City of
San Diego**

Sediment Control: Storm Drain Inlet Protection BMP

- ❖ **Dry Weather** – implement at all inlets receiving runoff from active construction areas.
- ❖ **City ROW** – remove prior to rain or during emergency water main breaks to prevent flooding. Remove prior to end of day or weekend if rain is in forecast and replace prior to restarting construction.



Storm Drain Inlet Protection

- You are Responsible for the Project
- CGP Required Sediment Controls – Perimeter and Sweeping
- Inlet Protection – Drains Erodible Area (Construction)
- Limitations –
 - Ponding Shall Not Encroach into Traveled Way or Overtop Curb or Dike ***
 - Inlet Protection Shall Not Be an Obstacle - Bicyclist Hindrance
- Often Broken Bags
- Often Removed During Storms

*** Section 16.03C Temporary Drainage Inlet Protection

Soil Cover on Active DSAs

- Current General Construction Permit

Inactive DSAs – All Risk Levels

D. Erosion Control

2. Risk Level 2 dischargers shall provide effective soil cover for inactive¹ areas and all finished slopes, open space, utility backfill, and completed lots.

¹ Inactive areas of construction are areas of construction activity that have been disturbed and are not scheduled to be re-disturbed for at least 14 days.

Soil Cover on Active DSAs

- Current General Construction Permit
Active DSAs – Risk Level 2 & 3

E. Sediment Controls

3. **Additional Risk Level 2 Requirement:** Risk Level 2 dischargers shall implement appropriate erosion control BMPs (runoff control and soil stabilization) in conjunction with sediment control BMPs for areas under active² construction.

² Active areas of construction are areas undergoing land surface disturbance. This includes construction activity during the preliminary stage, mass grading stage, streets and utilities stage and the vertical construction stage.

Soil Cover on Active DSAs

- Current General Construction Permit

I'm no Lawyer, what does footnote 2 mean? Depends who is interpreting

My thoughts:

APPROPRIATE Erosion Control

1. Control DSA for wind erosion - Constantly
2. Control DSA for water erosion – Directly before a rain event.

One is out of CGP compliance when an event produces runoff upon uncovered DSAs.

QRE equals sampling.



Soil Cover on Active DSAs

- Current General Construction Permit

What does footnote 2 mean to others?

Here is what I have heard – San Diego RWQCB:

APPROPRIATE Erosion Control

1. Control DSA for wind erosion - Constantly
2. Control DSA for water erosion – At the End of Each and Every Work Day, cover DSA with plastic.

QRE equals sampling.



Soil Cover on Active DSAs

- How do we comply?

Monitor the weather

Rain event is coming. What now?

1. Scheduling
2. Hydraulic Mulch – Cure period
3. Hydroseeding – Growth period
4. Straw Mulch - Studded roller or tackifier.
5. Plastic – Large area prohibitive

Must Be
Removed

Nope!!!

Time
to
Cure

Organics

Constant
Agitation

Multi-Steps

Guar/Xanthan Gum
Starch

Soil Cover on Active DSAs

- Okay, what does work?

Synthetic (chemical) Tackifiers

Vinyl Copolymers

1. Soiltac
2. Gorilla-Snot

Polyacrylamides

1. LiquiTack
2. PM50/PM70
3. EarthGuard

Chemical

Water Truck

24 hour Cure

One Step

Left In Place

During Rain

**5 gallon versus
55 or 275
gallon Totes**

Annual Report & Monitoring Documentation

XVI. ANNUAL REPORTING REQUIREMENTS

- A. All dischargers shall prepare and electronically submit an Annual Report no later than September 1 of each year.
- B. The discharger shall certify each Annual Report in accordance with the Special Provisions.
- C. The discharger shall retain an electronic or paper copy of each Annual Report for a minimum of three years after the date the annual report is filed.
- D. The discharger shall include storm water monitoring information in the Annual Report consisting of:
 - 7. the date, place, time of facility inspections, sampling, visual observation (inspections), and/or measurements, including precipitation (rain gauge); and
 - 8. the visual observation and sample collection exception records and reports specified in Attachments C, D, and E.

Annual Report & Monitoring Documentation

6. Risk Level 3 – Visual Observation and Sample Collection Exemptions

- a. Risk Level 3 dischargers shall be prepared to collect samples and conduct visual observation (inspections) until the minimum requirements of Sections I.3 and I.4 above are completed. Risk Level 3 dischargers are not required to physically collect samples or conduct visual observation (inspections) under the following conditions:
 - i. During dangerous weather conditions such as flooding and electrical storms.
 - ii. Outside of scheduled site business hours.
- b. If no required samples or visual observation (inspections) are collected due to these exceptions, Risk Level 3 dischargers shall include an explanation in their SWPPP and in the Annual Report documenting why the sampling or visual observation (inspections) were not conducted.

Annual Report & Monitoring Documentation

D. GOOD SITE MANAGEMENT "HOUSEKEEPING" [CGP Attachment D, Section B]

1. Were required good site management "housekeeping" measures for construction materials fully implemented on-site?

☐

YES

☐

NO

If NO Explain: _____

F. EROSION CONTROLS [CGP Attachment D, Section D]

1. Were required erosion controls fully implemented on your site?

☐

YES

☐

NO

If NO Explain: _____

G. SEDIMENT CONTROLS [CGP Attachment D, Section E]

1. Were required sediment controls fully implemented on your site?

☐

YES

☐

NO

If NO Explain: _____

Annual Report & Monitoring Documentation

H. RUN-ON AND RUN-OFF CONTROLS [CGP Attachment D, Section F]

1. Was all site run-on and run-off effectively managed?

☐ YES

☐ NO

If NO, Explain: _____

I. RAIN EVENT ACTION PLAN (REAP) [CGP Attachment D, Section H]

1. Were REAPs developed 48 hours prior to all likely precipitation events (50% or greater probability of producing precipitation)?

☐ YES

☐ NO

If NO, Explain: _____

J. INSPECTION, MAINTENANCE AND REPAIR [CGP Attachment D, Section G]

2. Were site inspections conducted weekly and at least once each 24-hour period during extended storm events?

☐ YES

☐ NO

If NO, Explain: _____

Annual Report & Monitoring Documentation

K. VISUAL MONITORING [CGP Attachment D, Section I.3]

1. Were all storm water discharges that occurred at all discharge locations observed within 2 business days (48 hours) after each qualifying rain event (producing precipitation of $\frac{1}{2}$ inch or more at the time of discharge)?

☐

YES

☐

NO

If NO, Explain: _____

3. Were the time, date, and rain gauge reading recorded for each qualifying rain event?

☐

YES

☐

NO

If NO, Explain: _____

4. Within 2 business days (48 hours) prior to each predicted qualifying rain event, were visual inspections conducted in compliance with **CGP Attachment D, Section I.3.e&f**?

☐

YES

☐

NO

If NO, Explain: _____

Annual Report & Monitoring Documentation

L. WATER QUALITY SAMPLING AND ANALYSIS [CGP Attachment D, Section I.4]

1. How many qualifying storm events (producing precipitation of ½ inch or more at the time of discharge) occurred this past reporting year? _____
2. How many qualifying storm events (producing precipitation of ½ inch or more at the time of discharge) were sampled? _____

Explain Un-sampled events: _____

2011-2012
RISK LEVEL 2 ANNUAL REPORT
FOR
STORM WATER DISCHARGES ASSOCIATED
WITH CONSTRUCTION ACTIVITIES (RISK LEVEL 2)

Reporting Period **July 1, 2011** through **June 30, 2012**

In compliance with the Construction General Permit (CGP) an annual report is required to be submitted electronically via SMARTS by September 1 of each year. This document must be certified and signed, under penalty of perjury, by the appropriate official of your company.

If you have any questions, please contact your Regional Board Storm Water Permit Contact. The names, telephone numbers and e-mail addresses of the Regional Board contacts, as well as the Regional Board office addresses can be found at http://www.waterboards.ca.gov/waterboards_map.shtml. To find your Regional Board information, match the first digit of your WDID number with the corresponding number that appears in parenthesis on the first line of each Regional Board office.

Annual Report & Monitoring Documentation

STATE OF CALIFORNIA • DEPARTMENT OF TRANSPORTATION

WEATHER MONITORING LOG

CEM-2041 (REV. 3/2013)

PROJECT INFORMATION NAME AND SITE ADDRESS	CONTRACT NUMBER
	PROJECT IDENTIFIER
	WDID NUMBER
CONTRACTOR NAME AND ADDRESS	PROJECT SITE RISK LEVEL
	<input type="checkbox"/> Risk Level 1 <input type="checkbox"/> Risk Level 2 <input type="checkbox"/> Risk Level 3
SUBMITTED BY CONTRACTOR (PRINT AND SIGN NAME)	
WEEKLY REPORTING PERIOD Week of / / - / /	

STATE OF CALIFORNIA • DEPARTMENT OF TRANSPORTATION

STORMWATER SITE INSPECTION REPORT

CEM-2030 (REV 3/2014)

PROJECT INFORMATION NAME AND SITE ADDRESS	CONTRACT NUMBER
	PROJECT IDENTIFIER
	WDID NUMBER
CONTRACTOR NAME AND ADDRESS	PROJECT SITE RISK LEVEL
	<input type="checkbox"/> Risk Level 1 <input type="checkbox"/> Risk Level 2 <input type="checkbox"/> Risk Level 3
Submitted by contractor (print and sign name)	



Your National Weather Service forecast

Burbank CA

Enter Your "City, ST" or zip code

NWS Los Angeles/Oxnard, CA

Point Forecast: Burbank, CA

34.21°N 118.31°W (Elev. 1194 ft)

Mobile Weather Information | En Español

Last Update: 2:18 pm PDT Jul 30, 2010

Forecast Valid: 4pm PDT Jul 30, 2010-8pm PDT Aug 6, 2010

Forecast at a Glance

Tonight	Saturday	Saturday Night	Sunday	Sunday Night	Monday	Monday Night	Tuesday	Tuesday Night
								
Mostly Clear Lo 59 °F	Sunny Hi 80 °F	Mostly Clear Lo 59 °F	Sunny Hi 81 °F	Mostly Clear Lo 60 °F	Sunny Hi 83 °F	Mostly Clear Lo 61 °F	Sunny Hi 88 °F	Mostly Clear Lo 62 °F

STATE OF CALIFORNIA • DEPARTMENT OF TRANSPORTATION

STORMWATER CORRECTIVE ACTIONS SUMMARY

CEM-2035 (REV 11/2013)

PROJECT INFORMATION NAME AND SITE ADDRESS	CONTRACT NUMBER/CO/RTE/PM
	PROJECT IDENTIFIER NUMBER
	WDID NUMBER
CONTRACTOR NAME AND ADDRESS	SWPPP PROJECT SITE RISK LEVEL
	<input type="checkbox"/> Risk Level 1 <input type="checkbox"/> N/A <input type="checkbox"/> Risk Level 2 <input type="checkbox"/> N/A <input type="checkbox"/> Risk Level 3 <input type="checkbox"/> Hyd. No.
Submitted by contractor (print and sign name)	

Annual Report & Monitoring Documentation



- Weather Alerts
- Easy Distribution of Reports
- Electronic, Fillable Forms
- Inspections Auto-Documented

☐ Risk Level 2
☐ Risk Level 3

☐ LUP Type 2
☐ LUP Type 3

Submitted by (Print Name and Sign):

Date:

Water Pollution Control Manager Name and Company Name:

Phone Number:

Emergency (24/7) Phone Number:

General Information

Inspector's Name:

Date of Inspection:

Weather Condition:

Precipitation Condition:

Wind Condition:

Construction Phase:

Site Information:

Project Status:

☐ Compliance
☐ Substantial Compliance – Minor Deficiencies Noted

☐ Non-Compliance – Major Deficiencies or Discharge(s) noted
☐ Contractor was notified of deficiencies
 Prompt Action is Required
 Date:

Stormwater Site Inspection Requirements

Perform the following visual inspections of the project site:

Item No.	Activity	Yes	No	N/A	Notes
1	SWPPP Documentation Review:				
1a	Does the SWPPP contain all the required information?				
1b	Are the SWPPP Site Maps on the wall (where applicable) and kept current reflecting the status of the project and the location of all BMPs?				
1c	Does the SWPPP need to be amended?				
1d	Are all of the reports on file?				

Complete Package
for
Field Compliance

Stormwater Form Tracking Sheet													
Sample Project													
Week Of	4/11	4/18	4/25	5/2	5/9	5/16	5/23	5/30	6/6	6/13	6/20	6/27	7/4
Contractor Site Inspection Reports													
Weekly	X	X	X	X	X	X	X	X	X	X	X	X	X
Pre-Storm						X			X				
During Storm						X			X				
Post Storm						X				X			
Quarterly Inspection							X						
Corrective Action Summary	X		X	X		X	X		X	X			
Quarterly Amendments													
Training Logs	X	X	X	X	X	X	X	X	X	X	X	X	X
Weather Monitoring Logs	X	X	X	X	X	X	X	X	X	X	X	X	X
Notice of Discharge Reports													

Annual Report & Monitoring Documentation

- Weather Alerts
- Historical NOAA Weather Reports

Management Package





PROJECTS

[How It Works](#)
[Contact Us](#)
[Account Settings](#)
[Logout](#)

Active Projects

Archived Projects

ADD A NEW PROJECT +

PROJECT NAME	LOCATION	WED 11/14	THU 11/15	FRI 11/16	SAT 11/17	SUN 11/18	MON 11/19
Fresno Project	Fresno	0% / 0"	0% / 0"	0% / 0"	0% / 0"	0% / 0"	0% / 0"
Los Angeles Project	Anaheim	0% / 0"	0% / 0"	0% / 0"	0% / 0"	0% / 0"	5% / 0"
Sacramento Project	Sacramento	0% / 0"	0% / 0"	0% / 0"	0% / 0"	0% / 0"	5% / 0"

[Terms & Conditions](#)
[Privacy Policy](#)
 Copyright 2017 Stormlogger. All rights reserved.

Sacramento Project

Created 10/11/2018

<div>Wednesday</div> <div>0 %</div> <div>0"</div> <div>3 mph</div> <div>-° 68°</div>	<div>Thursday</div> <div>0 %</div> <div>0"</div> <div>1 mph</div> <div>37° 69°</div>	<div>Friday</div> <div>0 %</div> <div>0"</div>	<div>Saturday</div> <div>0 %</div> <div>0"</div>
<div>Today's Forecast</div>		<div>THURSDAY</div> <div>WIND</div> <div>TEMP</div> <div>RAINFALL</div>	
TIME	WEATHER	CHANCE	PRECIP
4 AM		0 mph	40° 0%
10 AM		1 mph	55° 0%
4 PM		1 mph	65° 0%
10 PM		1 mph	48° 0%

Sacramento Project

Forecast For Lat/Lon: 38.5687132/-121.384135
Sacramento CA

Data downloaded from <http://www.wrh.noaa.gov> at 02:02 am on 11/14/18

	Wed Nov 14				Thu Nov 15				Fri Nov 16				Sat Nov 17				Sun Nov 18				Mon Nov 19			
Daily-Temp	High: 68.0°				High: 68.0°				High: 70.0°				High: 67.0°				High: 66.0°				High: 66.0°			
	Low: 37.0°				Low: 38.0°				Low: 39.0°				Low: 39.0°				Low: 37.0°				Low: 38.0°			
Chance of Precip	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	5%	5%
Precip	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"	0.0"

Annual Report & Monitoring Documentation




- Weather Alerts
- Project Weather – Summary Form
- Documents Required Monitoring Events with “Should Have Been Done” Logs

Management Package For Monitoring Compliance

Enter the email addresses of the individuals that you would like to receive email alerts of forecast and precipitation event information:

Email Address	Email Alerts	Write logs	View Reports
Nobody		<input checked="" type="radio"/>	
Email Address No. 1: <input type="text"/>	<input type="checkbox"/>	<input type="radio"/>	<input type="checkbox"/>
Email Address No. 2: <input type="text"/>	<input type="checkbox"/>	<input type="radio"/>	<input type="checkbox"/>

RainCheQ Rainfall Alert - Zipcode:91901 - Alpine Creek Drainage Inbox x

 RainCheQ <info@raincheq.com>
to me ▾

Good Morning RainCheQ Customer,

Precipitation has been detected for your project or facility in the past 48 hours. Depending on the total amount rain, and your business hours, a Daily During Extended Rain Event Site Inspection or post-ORE Visual Observ keep you apprised of the weather and the potential need for additional inspections and/or visual observations follows:

Weather Station ID: E3263

Precipitation Minus 2-Day: 0.74 inches (Date From:09-20-2016 0100 AM – Date To:09-21-2016 1200 AM)
[View Report](#)

Weather Data	Jan 01	Jan 02	Jan 03	Jan 04	Jan 05	Jan 06	Jan 07
48-hour Forecast (to this date)	0%	6%	41%	52%	95%	80%	60%
24-hour Forecast (to this date)	0%	8%	50%	70%	100%	94%	49%
Current Day Forecast (this date)	0%	8%	57%	58%	100%	100%	52%
Start Time (Approximate)	NA	NA	NA	NA	0500 AM	1100 AM	0100 AM
End Time (Approximate)	NA	NA	NA	NA	0500 PM	1100 PM	0800 AM
Precipitation Amount (inches)	0.00	0.00	0.00	0.00	2.47	1.13	0.33
Weather Data	Jan 08	Jan 09	Jan 10	Jan 11	Jan 12	Jan 13	Jan 14

Time Period or Date of Required Inspection / Observation	Inspection / Observation Type	Was Required Inspection / Observation Conducted?	If Not, State Reason	Action
June 30 - July 06, 2016	Weekly	<input checked="" type="radio"/> Yes <input type="radio"/> No		<button>Submit</button>
July 07 - 13, 2016	Weekly	<input checked="" type="radio"/> Yes <input type="radio"/> No		<button>Submit</button>
July 14 - 20, 2016	Weekly	<input checked="" type="radio"/> Yes <input type="radio"/> No		<button>Submit</button>

Constructability / Budget Review

- Public Works Construction - Caltrans

- Soil Cover Quantities:
Active and Inactive
- Perimeter Control Quantities;
Perimeter Control, Face of Slope Interrupters
- Run-On/-Through Control Quantities:
Check Dams, Other?

2018
CONTRACT COST DATA
A SUMMARY OF COST BY ITEMS FOR
HIGHWAY CONSTRUCTION PROJECTS

Don't forget about various stages, and multiple seasons

Constructability / Budget Review

- Public Works Construction - Caltrans
 - Stabilized Construction Entrances
 - Concrete Washouts
 - Street Sweeping
- REAPs
- Storm Water Sampling and Analysis Day
- Storm Water Annual Report



Don't forget about various stages, and multiple seasons

Do Not Implement Regulatory Insurance

- Last Thought on Drainage Inlet Protection in Public Areas



Questions for the Speakers?

Ali.Pirouzian@sdcounty.ca.gov

David.Sluga@TRCcompanies.com

Up-and-Coming QSPs
Learning about Drainage
Inlet Protection

Continuing Education Credit

A credit value is assigned to CMAA courses and seminars in units of Professional Development Hours (PDH), Learning Units (LU), and CCM Recertification Points. CMAA guarantees that course material meets the minimum requirements for a PDH, which is 60 minutes of instruction, or increments thereof.



All courses approved by CMAA count toward CCM recertification points. For more information on recertification points, please visit

<https://recerttrack.com/home.php?portal=24>



CMAA is registered with the American Institute of Architects (AIA) as an approved CES provider of LUs. One educational contact hour equals one (1) LU. To receive LUs through CMAA, you must provide your AIA member number on all registration materials and attendance forms.

www.aia.com



CMAA has met the standards and requirements of the Registered Continuing Education Program. Credit earned on completion of this program will be reported to RCEP. A certificate of completion will be issued to each participant. As such, it does not include content that may be deemed or construed to be an approval or endorsement by RCEP.

www.rcep.net

Not all sessions and activities offered may be acceptable for continuing education credit in your state. Please check your state licensing board's requirements before submitting your credits.

